

Tabela robót ziemnych

Budowa drogi gminnej w Kiskowie ul. Wiśniowa - Morelowa - Śliwowa - Czereśniowa

ul. Wiśniowa

KM	POWIERZCHCNIA	POWIERZCHNIA ŚREDNIA	ODL.	OBJĘTOŚĆ	UWAGI
	m ²	m ²	m	1,03 x m ³	
3,00	8,330				
		6,125	22,00	138,79	
25,00	3,920				
		4,255	25,00	109,57	
50,00	4,590				
		4,895	25,00	126,05	
75,00	5,200				
		5,245	25,00	135,06	
100,00	5,290				
		5,085	25,00	130,94	
125,00	4,880				
		4,370	25,00	112,53	
150,00	3,860				
		4,005	25,00	103,13	
175,00	4,150				
		4,180	25,00	107,64	
200,00	4,210				
		4,130	25,00	106,35	
225,00	4,050				
		4,270	25,00	109,95	
250,00	4,490				
		4,755	25,00	122,44	
275,00	5,020				
		5,105	25,00	131,45	
300,00	5,190				
		5,355	25,00	137,89	
325,00	5,520				
		4,705	25,00	121,15	
350,00	3,890				
		3,785	25,00	97,46	
375,00	3,680				
		3,985	25,00	102,61	
400,00	4,290				
		4,180	25,00	107,64	
425,00	4,070				
		4,635	25,00	119,35	
450,00	5,200				
		4,050	29,05	121,18	
479,05	2,900				
		2,980	24,40	74,89	
503,45	3,060				
		3,770	21,55	83,68	
525,00	4,48				
		2,240	0,00	0,00	
		SUMA		2 399,75	